BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2012-13/RD/WORK_INDENT4210/CALL-4

APPROVED SCHEDULE - B

Tender Notification No:EE/BTP/BBMP/E-PMT/19/2013-14, Date: 07.02.2014

Improvements of side drains and drains in ward no. 08 at Kodigehalli sub division

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of NARASARAJU C	
				In Figures	In Words
1	122.37	KSRB 300.2 : Earthwork excavation by manual means in Hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface levelled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. complete as per specifications.	cum	76.98	Rupees Seventy Six and Ninety Eight Paise Only
2	22.94	KSRRB 2900-4.1: Providing and laying in position plain cement concrete mix 1:4:8 with stone aggregate 40mm and down size in foundation upto a depth of 2m below ground level and upto a height of 1.5m above ground level / bed level machine mixed, concrete laid in layers not exceeding 15cms thick well compacted, cost of all materials, labour, HOM of machineries, curing complete as per specifications.	cum	3315.59	Rupees Three Thousand Three Hundred Fifteen and Fifty Nine Paise Only
3	458.88	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness,, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specificaitons.	Sqm	197.80	Rupees One Hundred Ninety Seven and Eighty Paise Only
4	53.54	KSRB 4.2.2 : Providing and laying in position reinforced cement concrete of mix 1:1.5:3 with 20mm and down size graded granite metal, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth and ground floor level for retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications.	cum	4853.10	Rupees Four Thousand Eight Hundred Fifty Three and Ten Paise Only
5	48.18	KSRB 4.9.2 : Providing T.M.T. Steel reinforcement for R.C.C. work including straightening, cutting, bending, hooking , placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.	Qtl	5152.47	Rupees Five Thousand One Hundred Fifty Two and Forty Seven Paise Only

122.37	Lead for disposal of debris shall be payable at Carriage rates by mechanical means with all lead and lift, loading, undloading and labour charges etc.,complete and as per the directions of the Engineer-in-charge of the work.	cum	66.65

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92